ITEMS BY OWNER / GENERAL CONTRACTOR

35 - 37 - Door Finishes

Tag	Description	Interior Finish	Interior Frame Finish	Exterior Finish	Exterior Frame Finish	Contact	Comments
35	Women's/Men's Restroom Door	LMXX: Arborite, W464-EV Blonde Modern Cherry	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	LM70: Lamitech, 3156 Grey Slate	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	Universal Manufacturing: Vincent Holland, 800.821.1414 x106	Vertical grain direction on all wood laminated doors.
36	Restroom Stall Door	LMXX: Arborite, W464-EV Blonde Modern Cherry	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	LMXX: Arborite, W464-EV Blonde Modern Cherry	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	Universal Manufacturing: Vincent Holland 800.821.1414 x106	Vertical grain direction on all wood laminated doors.
37	Mop Closet Door	LM70: Lamitech, 3156 Grey Slate	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	LM70: Lamitech, 3156 Grey Slate	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	Universal Manufacturing: Vincent Holland 800.821.1414 x106	Vertical grain direction on all wood laminated doors.
38	Fast Forward Door	per MCDs specifications	per MCDs specifications	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	PT06: Benjamin Moore, 2134-30 Iron Mountain (Semi-Gloss)	Universal Manufacturing: Vincent Holland 800.821.1414 x106	--

Items Per A/E Construction Docs (For Reference Only)

Description (If Applicable)	Contact	Comments
BOH	See Architectural Drawings	--
Service Counter	If required, request an order form from McDonald's Central Purchasing	Due to processing time, allow up to 7 weeks lead-time from placement of order to on site delivery.
McCafe Cell	If required, request an order form from McDonald's Central Purchasing	--
Curated Views Kit (If Required)	If required, request an order form from McDonald's Central Purchasing	Due to processing time, allow up to 3 weeks lead-time from placement of order to on site delivery. ISI is not responsible for determining placement. Consult McDonald's guidelines for any scope or placement questions.

45 - Reverse Beverage Station

Tag	Description	Dining side Access Door and Soffit above	Counter Finish	Corian Contact	Kitchen Side Access Doors	Kitchen Side Access Doors	Comments
45	Reverse Beverage Station and Trash Counter Top	SS17: Dupont, Corian, Deep Titanium	SS14: Dupont, Corian, Cameo White	Dupont, Local Distributor	LMXX: Wilsonart, D9 Dove Gray	Dan Chickvara, Dan.Chickvara@wilsonart.com, 770.335.3982	--

46 - Restroom Finishes

Tag	Description	Style	Vanity Finish	Faucet	Hand Dryer Backer Finish	Contact	Comments
46	Restroom Fixture Finishes	Per McDonald's Architectural details	SS14: Dupont, Corian, Cameo White	Per McDonald's Architectural specifications	SS14: Dupont, Corian, Cameo White	Dupont, Local Distributor	G.C. to refer to McDonald's architectural drawings for restroom fixture specifications and details.

48 - Corner Guards

Tag	Description	Finish	Contact	Comments
48a	Restroom Corner Guards	TR03: Schluter Systems LP, RONDEC-AE Satin Anodized Aluminum	Earl Maicus 800.267.0817 ext. 3410	G.C. is responsible for ordering all necessary connectors and inside/outside trims for installation.
48b	Service Area Corner Guards	TR07: Schluter Systems LP, 5/16" Quadec Trim / Tuscan Pewter Q80TSG	Earl Maicus 800.267.0817 ext. 3410	G.C. is responsible for ordering all necessary connectors and inside/outside trims for installation.

49 - Electrical Outlets

Tag	Description	Receptacle Plate Finish	Comments
49	Tamper Resistant GFCI receptacles	Grey	To be mounted at designated heights & locations

53 - Transom Laminate Panel System

Tag	Comments
53	GC to install Transom Laminate Panel System to be provided by ISI. Installation instruction available upon request.

55 - Restroom Signage

Tag	Description	Contact	Comments
55	Men's & Women's Restroom Signage	Forrest Perma Signs, www.forrestpermasigns.com, 1.800.214.8765	--

56 - Kiosks

Tag	Count	Description	Contact	Comments
56	2	Double Sided - Kiosk	Per Owner/GC	Electrical and data from ceiling for Kiosks

58 - GC Half Wall Top Cap

Tag	Description	Finish	Contact	Comments
58	1" Thick Corian Top Cap for GC Halfwall	SS13: Dupont, Corian, Deep Mink	Dupont, Local Distibutor	Top cap to overhang GC halfwall by 1-1/2" on all sides

501 W Sunshine | Springfield, MO | Site ID: 240007 | National Number: 135
RMM: Rachel Wise | PM: Rick Treleven | Design: Rachel Pollex | CAD: VDR, NS | Job #: 112507
Portfolio: Wood & Stone Global

INTERIOR SYSTEMS™ Inc

think. create. build.

Milwaukee, WI | Fond du Lac, WI

REV	DATE	DESCRIPTION	BY
1	02/22/19	Kiosk Review Revisions and Approval	RP
	03/01/19	Permit Set Created	RP
2	03/25/19	Bid Set Created/Arch Update: Vestibules, SC and Kiosk Review Revision and Re-Approval	JC/RP

BID SET
NOT FOR CONSTRUCTION

GC Specifications